BRUHATH BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work : Construction of concrete drain at 1st Cross Bhoomika Layout (Kirloskar Layout 1st Main Deaddend) in Bagalagunte in ward No. 14 T.Dasarahalli sub Division

Sl. No	Description	Unit	Qty	Rates	
				In Figs	in Words
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification conveying the excavated earth slit debris and over burden earth etc., to lead of 0 to 5kms distance by using private vehicle this includes the cost of loading and unloading crharges etc., complete as per the direction of engineer	Cum	559.80	170.92	Rupees one hundred seventy and ninety two paise only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications.	Cum	69.97	5159.02	Rupees five thousand, one hundred fifty nine and zore two paise only
3	Design mix M 20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008 i) upto 5m height	Cum	135.28	6965.26	Rupees six thousand, nine hundred sixty five and twenty six paise only
4	Supplying, fitting and placing TMT bar reinforcement in sub-structure as per drawing and Technical Specifications complete as per specifications. MORTH Specification No.1600 & 2200 TMT Bars FE 500	Tonne	8.77	58090.12	Rupees fifty eight thousand, ninety and twelve paise only

EXECUTIVE ENGINEER-4
RMDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl No	Description	Unit	Qty	Rates	
				In Figs	In Words
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	1244.00	310.58	Rupees three hundred ten and fifty eight paise only
6	Supplying and fixing precast reinforced conceret slabs 10cm thick of mix M20 using 20mm and sownsize graded grantite metal using reinforecement 100mm dia steel at 150mm C/C both ways cost, transportation, hire charges of machinerym machine cuttng the vertical face to get plain even surface etc., complete with all lead and lift conveyance charges, labour charges inclusive of cost of all materials	Sqm	279.90	1600.00	Rupees one thousand, six hundred only

EXECUTIVE ENGINEER-4
RIDL, BDA CAMPUS
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Signature of the Contractor

Executive Engineer
Dasarahalli Division